BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED TENDER SCHEDULE –'B'

Name of Work: - Development and improvements to roads and drains in ward no03 Attur area surroundings in Yelahanka Upanagara sub division.

Sl	Description	Unit	Approved Qty	Approved Rates	
				Rate	Rate in Words
1	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3. No. 141/ Item No. 19.1/ PWD SR 2015-16	Cum	515.04	83.16	Rupees eighty three and paise sixten only
2	Removing B.S slab of drain and stacking(P.no25/s.no5.32)	Sqm	332.64	63.72	Rupees sixty three and paise seventy two only
3	Refixing stone slabs of drains and pointing inCM(1:3) (p.no25/ s.no5.33)	Sqm	332.64	78.84	Rupees seventy eight and paise eighty four only
4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete do 7.5 cms thick	Sqm	1047.66	663.12	Rupees six hundred sixty three and paise twelve only
5	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m specification specification No	Cum	240.10	288.36	Rupees two hundred eighty eight and paise thrity six only
6	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exceeding	Cum	9.45	5070.60	Rupees five thousand seventy and paise sixty only

	Description	Unit	Approved Qty	Approved Rates	
				Rate	Rate in Words
7	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming etc as per specification&direction of the engineer incharge of work (pwd sr2015-16,p.no13,sno4.11)	Cum	52.17	6198.12	Rupees six thousand one hundred ninety eight and paise twelve only
8	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS4.6.3,TMT bars Fe55 0(pwd sr2015-16,p.no17,s.no4.46)	Tonnes	4.08	70509.96	Rupees seventy thousand five hundred nine and ninety six only
9	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters, bittresses, buttresses plinth and string course including cost of all materials,labour complete asperspecificationS.Specification no. KBS 4.6.2(pwd sr2015-16,p.no15/4.31)	Sqm	203.23	306.72	Rupees three hundred six and paise seventy two only
10	KSRRB M300-53 : Construction of embankment with approved material Gravel/Murrum with all lifts and leads, trasnporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications including cost of gravell/murrum,watering charges & compaction by vibratory roller to 95% of proctors density. MORTH Specification No. 305. (Page No. 147 & Item No. 19.60)	Cum	657.72	311.04	Rupees three hundred eleven and paise four only
11	KSRRB M1400-14.1. Providing, laying, spreading and compacting stone aggregates of granite/trap/basalt of specific sizes to water bound macadam specifications including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel / vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening / binding Materials to fill up the interstices of coarse aggregates, watering and compacting to the required density complete as per specifications.A.By manual means.Morth specification no.404,Type A 13.2 mm for grading II(P.156/I.20.14.1 PWD SR - 2015-16).	Cum	145.04	1751.76	Rupees one thousand seven hundred fifty one and paise seventy six only
12	KSRRB M1400-14.1. Providing, laying, spreading and compacting stone aggregates of granite/trap/basalt of specific sizes to water bound macadam specifications including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel / vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening / binding Materials to fill up the interstices of coarse aggregates, watering and compacting to the required density complete as per specifications.A.By manual means.Morth specification no.404,Type A 11.2 mm for grading III(P.156/I.20.14.1 PWD SR - 2015-16).	Cum	108.78	1867.32	Rupees one thousand eight hundred sixty seven and paise thirty tow only

Sl	Description	Unit	Approved Qty	Approved Rates	
				Rate	Rate in Words
1	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/ sand/ kanker/ Moorum. KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no 130, PWD SR 2016-17)	Cum	755.14	73.44	Rupees seventy three and paise forty four only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.